BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Name of Work :- Operation and Maintenance of street light fittings in Byatarayanapura ward no.10 Package Y-10 of Yelahanka Zone for the Period (10 Months).

Job Code : **P-Code: P0300**

Estimat Amount: 32.70 Lakhs **TS No:**

Sl. No	Description Of Work	Unit	Qty	Quoted Rates	In words
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **36/40 watt fluoroscent tube light street lighting systems.**	Each	20	405.00	Four Hundred Five Rupees
2	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day,Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **125 watt HPMV park lighting systems.**	Each	66	525.00	Five Hundred Twenty Five Rupees
3	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day,Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **250 watt HPSV street lighting systems.**	Each	2025	760.00	Seven Hundred Sixty Rupees
4	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **400 watt HPSV street light/high mast lighting systems.**	Each	36	835.00	Eight Hundred Thirty Five Rupees

For S.B.E.S. ELECTRICALS

S. Bhatt

Proprietor

5	Operation and Maintenance of LED street lighting system including replacement of damaged/failed /fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **24 to 45 watt LED street lighting System.**	Each	15	600.00	Six Hundred Rupees
6	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **50 to 72 watt LED street lighting systems.**	Each	36	795.00	Seven Hundred Ninety Five Rupees
7	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **90 watt LED street lighting systems.**	Each	566	950.00	Nine Hundred Fifty Rupees
8	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/ fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **100 to 120 watt LED street lighting systems.**	Each	428	1110.00	One Thousand One Hundred Ten Rupees

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For S.B.E.S. ELECTRICALS

Contractor S. Bhatt

Proprietor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone